Website: www.nitandhra.ac.in
Email: purchase@nitandhra.ac.in

राष्ट्रीय प्रौद्योगिकी संस्थान - आंध्रप्रदेश
NATIONAL INSTITUTE OF TECHNOLOGY ANDHRA PRADESH
Near National Highway No. 16, Kadakatla, Tadepalligudem – 534101
West Godavari District, Andhra Pradesh

Ref. No.: NITANP/SMMD/TENDER/2024-25/35 **Date**: 01.08.2024

TENDER ENQUIRY

Sub: Construction of RCC Chamber near STP 1 & 2 at NIT ANP Campus - Quotation invited –Regd.

Please send your lowest quotation for the above work as per the details attached in **Annexure-1**. The quotation is to be sent in a sealed envelope to the following address:

C/O TENDER BOX
MATERIAL MANAGEMENT & DISPOSAL SECTION,
SARDAR VALLABHBHAI PATEL ADMINISTRATIVE BUILDING
NATIONAL INSTITUTE OF TECHNOLOGY, ANDHRA PRADESH,
NEAR NATIONAL HIGHWAY NO. 16, KADAKATLA,
TADEPALLIGUDEM – 534101
WEST GODAVARI DISTRICT, ANDHRA PRADESH.

The quotation has to be sent by Post (Ordinary / Register / Speed Post) or drop in Tender Box physically. (Any other mode will not be accepted)

The envelope must be superscribed as "**QUOTATION**" at the center of the envelope and the above **reference number at left top** along with the name of the tender on the envelope. Quotations without the above superscription **will not be accepted**.

The last date to receive the sealed quotation is **21.08.2024**

Annexure-1

Name of the Work: Construction of RCC Chamber near STP 1 & 2 at NIT ANP Campus							
S.No	**Description**	**Nos**	**L**	**B**	**D**	**Qty**	**Units**
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.						
	All kinds of soil.	2	4	3	6	144	
		1	3	2	3	18	
						162	cum
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :						
	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :	2	4	3	0.3	7.2	
		1	3	2	0.3	1.8	
						9	cum
3	Centering and shuttering including strutting, propping etc. and removal of form for						
	Walls (any thickness) including attached pilasters, butteresses, plinth and string courses etc.					200	sqm
4	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :						
	1:1.5:3 (1 cement: 1.5 coarse sand (zone-III) derived from natural sources: 3 graded stone aggregate 20 mm nominal size derived from natural sources)					26	cum
5	**STEEL REINFORCEMENT**						
	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.						
	Thermo-Mechanically Treated bars of grade Fe-500D or more. K					2000	kg
6	Making connection of drain or sewer line with existing manhole including breaking into and making good the walls, floors with cement concrete 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) cement plastered on both sides with cement mortar 1:3(1 cement : 3 coarse sand), finished with a floating coat of neat cement and making necessary channels for the drain etc. complete :						
	For pipes 100 to 250 mm diameter	-	-	-	-	6	Nos
Provision for GI Coverplate							

Note: Bidder must have any one of below Registration Certificate.

(a) CPWD Class V Civil (or) above.

(b) Any State Government PWD Class V (Civil) (or) above.

While sending your lowest quotation – please specify the following:

1. Sales Tax : Inclusive
   GST : Indicate prevailing tax on percentage basis.
2. Excise Duty :
3. Rates
   a) F.O.R. Destination/
   b) Estimated Packing, Forwarding and Freight Charges in case of Ex-works only, may be mentioned on percentage basis.
4. Insurance : Inclusive/ indicate on percentage basis, in case payable by the Institute.
5. Preferred terms of payment (institute rules permit to pay on Receipt of materials in good condition/completion of the work):
6. Recommended mode of transport :
7. Discount offered, if any :
8. Validity of the offer :
9. Firm schedule of completion of work :
10. Detailed drawings / catalogues / Leaflets / literature / samples may be furnished wherever feasible / required.
11. Please indicate clearly whether the rates quoted herein are the same as applicable to DGS & D / Government Department / Other Public Sector Undertakings.
12. The supplier shall invariably furnish the **Certificate of Clearance of GST Registration number along with the quotations.**
13. The quotation should not contain any handwritten text except the Price quoted.
14. All the Submitted documents must be duly signed by the bidder along with the firm's seal.
15. Please mention the Quotation number and name of the item/s (in brief) on your envelope when submitting your quotation to the Institute
16. Please note that the Director reserves the right to modify or alter the specifications and also to reject any or all the Quotations without assigning any reasons thereto.
17. The suppliers / firms are informed not to call on us without prior appointment.
18. The Institute is not responsible for delays / loss in postal transit or due to any other reasons.
19. Any Violation in the terms and conditions, the bidder will be made ineligible for the contract.

National Institute of Technology राष्ट्रीय प्रौद्योगिकी संस्थान Andhra Pradesh आंध्रप्रदेश

Yours faithfully,

11/3/24

Head of the Department

सह अधिष्ठाता / Associate Dean
CENTRAL STORES & PURCHASE SECTION
NIT Andhra Pradesh